BANGALORE DIVISION.

Abstract Notification dated 14th December 1936.

The attention of the public is hereby invited to the detailed notification inviting tenders for the construction of the Administrative Block to the Veterinary Dispensary at Anekal published on pages 2037-2038, Part VI of the *Mysore Gazette*, dated 17th December 1936.

The last date for the receipt of the tender is 2 P.M. on 6th January 1937 and the earnest money to accompany the tender is Rs. 125.

Notification dated 14th December 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 12th January 1937, for the restoration of the breached Chickmuduvadi Gendikere Tank of Kankanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the restoration of the breached Chickmuduvadi Gendikere of Kankanhalli Taluk in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities of work for the restoration of the breached Chickmuduvadi Gendikere Tank, Register No. Nil, Kankanhalli Taluk.

Sl. No.	Items of work	Unit	Quantity	Rates sanctioned	Rate quoted in	
					Figures	Words
	Bund.			Rs. a. p.		
1	Jungle clearing with roots, etc.	Grade	12	2 0 0		
2	Cutting grips and steps	,,	12	2 0 0		
3	Earthwork to bund including watering and tamping with required lead and lift	C.yd.	4,450	0 3 6		
4	Turfing and watering till it is satisfactory	S.yd.	4,101	0 1 0		

Sl. No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
				Rs. a. p.		
5	Providing and fixing new grade stones with bed slabs, figures cut and painted, etc., complete	Each	15	2 0 0		
6	Do Index stone do ..	,,	15	0 6 0		
7	Do Registered number stone	,,	1	3 0 0		
8	Do Gauge stone do ..	,,	1	15 0 0		
9	Do B. M. stones do ..	,,	2	3 0 0		
10	New stone revetment with jelly wedging	C.yd.	991	1 12 0		
11	Dismantling old stone work and reconstructing with new jelly backing ..	,,	257	0 10 0		
12	Gravel backing with consolidation ..	,,	312	0 9 6		
	Breach filling.					
1	Cutting grips and steps	,,	138	0 3 6		
2	Clearing silt	,,	400	0 2 0		
3	Puddle wall	,,	220	0 8 0		
4	Earthwork in breach portion (good clay mixed with gravel) ..	,,	1,275	0 7 0		
	Waste Weir.					
1	Earthwork for excavating foundation	C.yd.	31	0 3 6		
2	Excavation in soft rock	,,	22	0 8 0		
3	Burnt brick in surki mortar ..	C.ft.	348	0 5 0		
4	Burnt stone slabs (6" thick) one line dressed and set in Surki mortar ..	S.ft.	137	0 6 0		
5	Surki mortar plastering	Sqr.	4	3 0 0		
6	Rough stone work for apron ..	C.yd.	33	2 0 0		
7	Benching rock	S.ft.	80	0 2 0		
8	Joggle joints for slabs	Each	12	0 8 0		
9	Draft approach clearing	C.yd.	562	0 3 6		
	Sluice.					
1	Earthwork cut opening bund and refilling with consolidation ..	C.yd.	88	0 6 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	161	0 4 0		
3	Burnt brick in surki mortar ..	,,	612	0 5 0		
4	Burnt stone slabs (6" thick) dressed and fixed in surki mortar ..	S.ft.	165	0 6 0		
5	Surki mortar plastering	Sqr.	5	3 0 0		
6	Providing and fixing plug iron rod with locking arrangement, etc., complete	Each	1	15 0 0		
7	Drilling holes in orifice slab	,,	4	0 12 0		

N. SUBBA RAO,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 10th December 1936.

"A Savings Bank Account No. 1544—S.D. containing a balance of Rs. 313-6-3 tendered by one Mr. A. Govindarajulu Naidu, son of Mr. Venkatachala Naidu, remains unclaimed in this office. If the Savings Bank Book is not claimed within three months from the date of this notification with sufficient evidence to prove the identity of the claimant the amount will be credited to Government."

D. KRISHNA RAO,
Executive Engineer.